


STANDARD SERIES 5-ROW 21' BLEACHER

MODEL 1171-521MESHG 5-ROW 21' STEEL WITH MESH GUARDRAIL
MODEL 1171-521MESHA 5-ROW 21' ALUMINUM WITH MESH GUARDRAIL

MODEL 1171-521VBGRG 5-ROW 21' STEEL WITH VBGR GUARDRAIL
MODEL 1171-521VBGRA 5-ROW 21' ALUMINUM WITH VBGR GUARDRAIL
(VBGR = VERTICAL BAR GUARDRAIL)

Standard Series designed for dependability and trouble-free maintenance. Featuring 6" rise from row to row with nominal 10" aluminum planks and optional 2" x 6" ground sills



SPECIFICATIONS:

Bleacher Frames are fabricated from 2" x 2" x 3/16" steel or aluminum angle. Frames are welded into a single unit. Frames may have optional 2" x 6" ground sills at every point where frames are in contact with the ground.

Standard Series Bleachers conform to the requirements of ICC 300-2012.

Seat and Foot Planks: Nominal 2" x 10" x 21' extruded, ribbed aluminum. The edges and tops of planks shall be ribbed. The ribbed pattern, non-slip surface, is designed for safety and comfort. All exposed ends shall have aluminum caps fastened to the underside of the plank. Planks secure to each frame with two friction-type aluminum mounting clips capable of securing the plank against movement under a horizontal force of 400 lbs. All hardware is provided.

Finish: All fasteners shall be zinc plated.



Date: 4/13/2021

Rev: A

Drawn: JBN

Sheet: 1 of 16

PRODUCT NAME


5 ROW STANDARD 21FT

MODEL NO.

1171-521

BOM PARTS & FASTENERS

ITEM NO.	PART NUMBER	DESCRIPTION	QTY.
1	ROW5A OR ROW5G	BLEACHER 5-ROW STANDARD FRAME	4
2	CIFFRAMES-LT	LEFT F-FRAME PANEL SUPPORT	1
3	CIFFRAMER	REAR F-FRAME PANEL SUPPORT	4
4	CIFFRAMES-RT	RIGHT F-FRAME PANEL SUPPORT	1
5	CIVBGRSIDE OR VCIMESH PANELSIDE	RAILING SIDE PANEL	2
6	CIVBGRREAR OR VCIMESH PANELREAR	RAILING LONG REAR PANEL	2
7	CIVBGRMID OR WMESH PANELMID	RAILING SHORT REAR PANEL	1
8	CIBLB76.375	BLEACHER BRACE 76-3/8" LONG	3
9	CIBLB74.625	BLEACHER BRACE 74-5/8" LONG	6
10	VCIPANELCLAMP138	1-3/8" X 1-3/8" PANEL CLAMP CLAMPS - PAIR	8
11	RMPLK21-10	ALUMINUM PLANK ANODIZED 10"x 252"	13
12	VCIAECP	2"x10" ALUM. END CAP	26
13	VCIACLP	BOLT CLIP FOR 10" & 12" ALUMINUM PLANK	104
14	HWCB5161	5/16-18 X 1 CARRIAGE BOLT GRADE 2 ZINC	88
15	HWCB38212	3/8-16 X 2 1/2 CARRIAGE BOLT ZINC (500)	8
16	HWCB5163	5/16-18 X 3 CARRIAGE BOLT ZINC (600)	16
17	HWFLWA516	5/16 FLAT WASHER	128
18	HWLN516	5/16 NYLOK NUT ZINC	128
19	HWUB516112	5/16 x 1-1/2 x 2-11/16 U bolt	12
20	HWFLWA38	3/8" FLAT WASHER	96
21	HWLN38	3/8"-16 LOCK NUT	48
22	HWHB38112	3/8-16 X 1 1/2 GR5 C/S ZINC HEX BOLT (1000)	40
23	HWTEX1034	#10 x 3/4 SELF TAPPING SCREW	52



Date: 4/13/2021

Rev: A

Drawn: JBN

Sheet: 2 of 16

PRODUCT NAME

5 ROW STANDARD 21FT


MODEL NO.

1171-521

INSTALLATION INSTRUCTIONS:

1) Check materials received with the BOM to make sure that all components are included and to assure that the unit is complete.

2) Installing End Caps Item on Seat and Foot Planks: 2" x 10" end caps Item (12) . Align and assemble all end caps to aluminum planks. Secure using #10 x 3/4" Item (23) self-tapping screw in two locations on the underside of the clip/plank.



Date: 4/13/2021

Rev: A

Drawn: JBN

Sheet: 3 of 16

PRODUCT NAME


5 ROW STANDARD 21FT

MODEL NO.

1171-521

INSTALLATION INSTRUCTIONS:

3) Locate the four Bleacher 5-Row Standard Frame Item ① and set on a level surface on 73" centers.



Date: 4/13/2021

Rev: A

Drawn: JBN

Sheet: 4 of 16

PRODUCT NAME

5 ROW STANDARD 21FT

MODEL NO.


1171-521

INSTALLATION INSTRUCTIONS: 1171-521

- 4) To Install Cross Braces: a) Locate three diagonal braces measuring 76 3/8" Item ⑨ and three horizontal braces measuring 74-5/8" ⑧.

Install on the backside of the Bleacher Frames using 3/8" x 1-1/2" Hex Bolt Item ②② , Washers Item ②① , and Lock Nut Item ②① provided using the top and bottom slots in the frame and center of Braces as shown. Repeat steps to assemble remaining sets of cross braces to the other bleacher frames. At all installation points, install washers and nuts but leave hardware loose until assembly is complete for easy installation.

NOTE: Two washers are provided to use at every hex bolt location.



Date: 4/13/2021

Rev: A

Drawn: JBN


Sheet: 5 of 16

PRODUCT NAME

5 ROW STANDARD 21FT

MODEL NO.

1171-521



DETAIL A
ENLARGED
FROM SHEET #5
SCALE 1 : 5



Date: 4/13/2021

Rev: A

Drawn: JBN

Sheet: 6 of 16

PRODUCT NAME

5 ROW STANDARD 21FT


MODEL NO.

1171-521

INSTALLATION INSTRUCTIONS:

5) To Install Cross Braces: a) Locate three horizontal braces measuring 74-5/8" Item (8) . Install on the backside of the second row of Bleacher Frames using 3/8" x 1-1/2" Hex Bolt Item (22) , Washers Item (20) , and lock nut Item (21) for the top, bottom slots and center between Braces. Repeat steps to assemble remaining sets of cross braces to the other bleacher frames. At all installation points, install washers and nuts but leave hardware loose until assembly is complete for easy installation.

NOTE: Two washers are provided to use at every hex bolt location.



ITEM (22) 11 QTY.

ITEM (20) 22 QTY.

ITEM (21) 11 QTY.



Date: 4/13/2021

Rev: A

Drawn: JBN


Sheet: 7 of 16

PRODUCT NAME

5 ROW STANDARD 21FT

MODEL NO.

1171-521



DETAIL B
ENLARGED
FROM SHEET #7
SCALE 1 : 3



Date: 4/13/2021

Rev: A

Drawn: JBN

Sheet: 8 of 16

PRODUCT NAME


5 ROW STANDARD 21FT

MODEL NO.

1171-521



INSTALLATION INSTRUCTIONS:

6) To Install Seat and Foot Planks: a) First install the Bolt Clip For 10" & 12" Aluminum Plank Item 13 using 5/16" x 1" carriage bolts Item 14 , washer Item 17 , and lock nuts 18 on top of the seat and foot board supports. To install clips for riser planks using 5/16" x 3" carriage bolts Item 16 , washer Item 17 , and lock nuts 18 .Give nuts about 3/4 turn (just enough to secure). Turn Bolt Clips Item 13 perpendicular to the frames.



Date: 4/13/2021
Rev: A
Drawn: JBN
Sheet: 9 of 16

PRODUCT NAME
5 ROW STANDARD 21FT
MODEL NO.
1171-521



Date: 4/13/2021

Rev: A

Drawn: JBN

Sheet: 10 of 16

PRODUCT NAME



5 ROW STANDARD 21FT

MODEL NO.

1171-521


INSTALLATION INSTRUCTIONS:

7) Position seat Planks, Foot Planks and Riser Planks on the supports so the Bolt Clips Item(13) are between the slots in the bottom of Planks. Reach up underneath the Seat Plank, Foot Plank, and Riser Plank to rotate the Bolt Clips Item(13) to 90° so they engage the planks. To Secure Planks to Frames center planks on frames Item(1) . Tighten all hardware on frames and planks securely.




FRONT VIEW

	Date: 4/13/2021	PRODUCT NAME 5 ROW STANDARD 21FT
	Rev: A	
	Drawn: JBN	MODEL NO. 1171-521
	Sheet: 11 of 16	




SECTION E-E
SCALE 1 : 15

BLOT CLIPS TURNED
90° TO ENGAGE PLANKS



DETAIL F
ENLARGED
SCALE 1 : 4

BLOT CLIPS TURNED
90° TO ENGAGE PLANKS



DETAIL G
ENLARGED
SCALE 1 : 3



Date: 4/13/2021

Rev: A

Drawn: JBN

Sheet: 12 of 16

PRODUCT NAME


5 ROW STANDARD 21FT

MODEL NO.

1171-521

INSTALLATION INSTRUCTIONS:

8) Install Right, Left and Rear F-Frame Panel Support Items (2) (3) (4) . Attach to Bleacher Frames with 3/8" x 1-1/2" hex bolts Item (22) , washers Item (20) and lock nuts Item (21) .



Date: 4/13/2021

Rev: A

Drawn: JBN

Sheet: 13 of 16

PRODUCT NAME


5 ROW STANDARD 21FT

MODEL NO.

1171-521


DETAIL-T

ENLARGED



DETAIL-U

ENLARGED



Date: 4/13/2021

Rev: A

Drawn: JBN

Sheet: 14 of 16

PRODUCT NAME


5 ROW STADARD 21FT

MODEL NO.

1171-521

INSTALLATION INSTRUCTIONS:

9) Install Railing Side and Rear Panels Items (5) (6) (7) . Attach Railing Side Panel Item (5) to Right F-Frame Panel Support Item (2) with 5/16" U-Bolt Item (19) ,washers Item (17) and lock nuts Item (18) Attach Railing Rear Long Panel Item (6) to Rear F-Frame Panel Support Item (3) using 5/16" U-Bolt Item (19) ,washers Item (17) ,lock nuts Item (18) , Panel Clamp Item (10) , 3/8" x 2-1/2" Carriage bolts Item (15) , washers Item (20) and lock nuts Item (21) . Repeat with the rest of the Railing Panels.



Date: 4/13/2021

Rev: A

Drawn: JBN


Sheet: 15 of 16

PRODUCT NAME

5 ROW STANDARD 21FT


MODEL NO.

1171-521




DETAIL-M

ENLARGED FROM
SHT. #15



DETAIL-L

ENLARGED FROM
SHT. #15



DETAIL-K

ENLARGED FROM
SHT. #15

INSTALLATION INSTRUCTIONS:

15) Installing (Optional) Ground Sills (wood measuring 2" x 6" x 8'-1"): a) Center one ground sill under each bleacher frame so the ends are evenly spaced and are centered from side to side. Mark the (4) hole locations in each bleacher frame on each of the ground sills and drill 1/4" x 1" deep pilot holes. DO NOT drill completely through the ground sills. b) Attach the ground sills to the bottom of the bleacher frames with 5/16" x 1-1/4" lag bolts and flat washers provided.



Date: 4/17/2021

Rev: A

Drawn: JBN

Sheet: 16 of 16

PRODUCT NAME

5 ROW STANDARD 21FT

MODEL NO.

1171-521